

CLEAR BAR END CAP

MATERIAL : POLYCARBONATE

CODE

RED : 506-1320020 BLACK : 506-1320050 WHITE : 506-1320080

APPLICATION

DAX 125 (JB04) ● FOR GENUINE HANDLE

- Thank you for purchasing Kitaco product. Read and understand the instruction before installing.

ATTENTION (MUST READ)

- This instruction sheet is for the instruction for genuine condition. Do not modify the way which is not listed or it will cause damage and trouble.
- We are not responsible for violation of law or damages and accidents caused by assembling mistake and improper setting.
- Please ask authorized mechanic for assembling and setting. Ask a specialist at specialty shop if you do not understand the role of the surrounding parts.
- Refer to the manufacturer service manual when installation.
- Bolts and nuts may get loosen by engine vibration. Make sure not to loosen any bolts and nuts before driving.
- Alumite product gets discolored/rust for ages as well as how to use. Please understand when using.

※The weight is different from genuine bar end, be careful of the handling right after the installation.


OTHER REQUIRED TOOLS

TAP M6 (P1.0)

SHOCK DRIVER

BAR END FIXING TOOL (RECOMMEND)

※BE CAREFUL OF SCRATCH WHEN FIXING.



CODE	NAME	QTY	REMARK
060-0500030	CAP BOLT M6x30	x2	
506-1154001	SPACER (FOR PRO)	x2	(SHORT)
-	CLEAR BAR END (RED)	x2	※When shipping, sticker is sticked.
-	CLEAR BAR END (BLACK)		
-	CLEAR BAR END (WHITE)		

HOW TO INSTALL

- Loosen the genuine bar end cap by using shock driver because genuine bar end cap installation bolt is hard to loosen. (If bar end rolls together, hold bar end while loosening bolt.)
- If the female screw of the handle side is broken, it needs to tap again by using M6 tap.
- Fix bar end cap firmly with attached bolt in the reverse order to removal.
- Recommend to apply screw lock to prevent loosening.

221214


株式会社 千七

〒 577-0015
3-8-13 NAGATA, HIGASHI-
OSAKA, OSAKA, JAPAN